




bre

**Testing of SmartDrain
and SlotDrain Linear
Drainage Units**


Prepared for: Mike Challinor
Manthorpe Building Products
Ltd, Manthorpe House, Brittain
Drive, Codnor Gate Business
Park, Ripley, Derbyshire
DE5 3ND

14th August 2013

Test report number 289 099



Prepared by

Name David Gall
Position Associate Director, Building Technology Group
Date 14th August 2013
Signature 

Approved on behalf of BRE


Name Martyn Webb
Position Principal Consultant, Building Technology Group
Date 14th August 2013


Signature

BRE
Garston
WD25 9XX
T + 44 (0) 1923 664000
F + 44 (0) 1923 664010
E enquiries@bre.co.uk
www.bre.co.uk


This report may only be distributed in its entirety and in accordance with the terms and conditions of the contract. Test results relate only to the items tested. BRE has no responsibility for the design, materials, workmanship or performance of the product or items tested. This report does not constitute an approval, certification or endorsement of the product tested.

This report is made on behalf of BRE. By receiving the report and action on it, the client – or any third party relying on it – accepts that no individual is personally liable in contract, tort or breach of statutory duty (including negligence).



Contents

1	Introduction	4
2	Details of tests carried out	6
3	Test results	9



1 Introduction

Following instruction from Mr Mike Challinor (Manthorpe Building Products Limited) BRE carried out testing of Class A15 SmartDrain and SlotDrain Linear Drainage Units.

Figures 1 and 2 show a schematic diagram of the SmartDrain and SlotDrain units respectively. The drainage unit was cast into concrete haunching, approximately 1200 x 320 x 190 mm (SmartDrain) and 1200 x 320 x 250 mm (SlotDrain), by the client.

The units were delivered to BRE on 29th July 2013 and tested on 12th August 2013. Present during the testing were Messrs Dave Brooke and David Gall (BRE), and Mr Ben Hales (Manthorpe Building Products Ltd.)




Figure 1: Schematic drawing of the SmartDrain Unit






Figure 2: Schematic drawing of the SlotDrain Unit



2 Details of tests carried out

The following testing was undertaken in accordance with BS EN 1433:2002 'Drainage channels for vehicular and pedestrian areas Classification, design and testing requirements, marking and evaluation of conformity'.


Watertightness

Three samples of the SmartDrain units were tested in accordance with clause 7.5.1. Each sample consisted of a 1m total length of SmartDrain channel body, supplied by Manthorpe Building Products Limited as being bonded together approximately half way along the length of the channel body according to the manufacturer's instructions, and haunched in a concrete casing of approximately 1200 x 320 x 190 mm. See Figure 3 below. The ends of the channel body were sealed by means of an end plate. The units were filled with water to the maximum designed wetted perimeter as indicated by the manufacturer's representative, and the units were inspected for any signs of leakage through the channel body and the joint, for a period of 30 minutes.

It should be noted that the SmartDrain and SlotDrain units comprise the same channel body and jointing method, therefore only one type of unit (in this case SmartDrain) was considered necessary to demonstrate the performance of the jointing method.



Figure 3: Photograph showing 2 of the 3 assemblies for watertightness test of channel body



Load bearing capacity

Various sized loading plates in accordance with Table 12 of EN 1433 were used to perform the permanent set testing in accordance with clause 7.16 and maximum load testing in accordance with 7.15.

The units were placed into a compressive test rig as shown in Figures 4 and 5 of this Report.

For the permanent set testing an initial datum point was established at the centre of the grating using a calibrated dial test indicator. After 5 applications of the permanent set load of 10kN a final reading of deflection of the grating was recorded and the permanent set of the grating was calculated as the difference between the initial and final readings.

For the maximum load testing the load was applied to achieve a target of 15kN. Upon reaching 15kN the load was maintained for a period of 30 seconds.



Figure 4: Photograph showing assembly for load test of SmartDrain unit





Figure 5: Photograph showing assembly for permanent set test of SlotDrain unit



3 Test results

Watertightness

SmartDrain Unit

Sample No	Specified	Actual	Assessment ⁽¹⁾
1	No visible leakage through the joint or body	No visible leakage through the joint or body	Pass
2		No visible leakage through the joint or body	Pass
3		No visible leakage through the joint or body	Pass


⁽¹⁾Following completion of the 30 minutes test period the units were re-inspected approximately 3 hours after the initial application of water into the test samples. There was no visible leakage through the joint or body.

Load bearing capacity

SmartDrain Unit

Permanent set

Sample No	Specified maximum permanent set (mm)	Actual permanent set (mm)	Assessment
1	1.94 max	0.36	Pass
2		0.41	Pass
3		0.57	Pass



Load bearing capacity (continued)

Maximum load (SmartDrain Unit)

Sample No	Specified	Actual	Assessment
1	Unit shall withstand the test load for 30 seconds without cracking or excessive deformation	Unit withstood the test load for 30 seconds without cracking or excessive deformation	Pass
2		Unit withstood the test load for 30 seconds without cracking or excessive deformation	Pass
3		Unit withstood the test load for 30 seconds without cracking or excessive deformation	Pass ⁽²⁾

⁽²⁾The unit was subsequently loaded to 60kN without cracking or excessive deformation

SlotDrain Unit

Permanent set

Sample No	Specified maximum permanent set (mm)	Actual permanent set (mm)	Assessment
1	0.40 max	0.04	Pass
2		Nil	Pass
3		Nil	Pass

Maximum load

Sample No	Specified	Actual	Assessment
1	Unit shall withstand the test load for 30 seconds without cracking or excessive deformation	Unit withstood the test load for 30 seconds without cracking or excessive deformation	Pass
2		Unit withstood the test load for 30 seconds without cracking or excessive deformation	Pass
3		Unit withstood the test load for 30 seconds without cracking or excessive deformation	Pass ⁽³⁾

⁽³⁾The unit was subsequently proof loaded. At approximately 25kN a hairline concrete crack appeared on the surface of the unit adjacent to the slots, however the unit was further loaded to 60kN without any further cracking of the concrete or excessive deformation.

=====REPORT ENDS=====